

ETSI TS 102 486-1-2 V1.2.1 (2008-10)

Technical Specification

**Intelligent Transport Systems (ITS);
Road Transport and Traffic Telematics (RTTT);
Test specifications for Dedicated Short
Range Communication (DSRC) transmission equipment;
Part 1: DSRC data link layer:
medium access and logical link control;
Sub-Part 2: Test Suite Structure and Test Purposes (TSS&TP)**



ReferenceRTS/ITS-0040006

Keywords

ITS, DSRC, DLC, MAC, LLC, protocol, radio,
testing, TSS&TP

ETSI

650 Route des Lucioles
F-06921 Sophia Antipolis Cedex - FRANCE

Tel.: +33 4 92 94 42 00 Fax: +33 4 93 65 47 16

Siret N° 348 623 562 00017 - NAF 742 C
Association à but non lucratif enregistrée à la
Sous-Préfecture de Grasse (06) N° 7803/88

Important notice

Individual copies of the present document can be downloaded from:

<http://www.etsi.org>

The present document may be made available in more than one electronic version or in print. In any case of existing or perceived difference in contents between such versions, the reference version is the Portable Document Format (PDF). In case of dispute, the reference shall be the printing on ETSI printers of the PDF version kept on a specific network drive within ETSI Secretariat.

Users of the present document should be aware that the document may be subject to revision or change of status. Information on the current status of this and other ETSI documents is available at

<http://portal.etsi.org/tb/status/status.asp>

If you find errors in the present document, please send your comment to one of the following services:

http://portal.etsi.org/chaicor/ETSI_support.asp

Copyright Notification

No part may be reproduced except as authorized by written permission.
The copyright and the foregoing restriction extend to reproduction in all media.

© European Telecommunications Standards Institute 2008.
All rights reserved.

DECT™, **PLUGTESTS™**, **UMTS™**, **TIPHON™**, the TIPHON logo and the ETSI logo are Trade Marks of ETSI registered for the benefit of its Members.

3GPP™ is a Trade Mark of ETSI registered for the benefit of its Members and of the 3GPP Organizational Partners.

Contents

Intellectual Property Rights	4
Foreword.....	4
1 Scope	5
2 References	5
2.1 Normative references	5
2.2 Informative references.....	6
3 Definitions and abbreviations.....	6
3.1 Definitions.....	6
3.2 Abbreviations	6
4 Test Suite Structure (TSS).....	6
4.1 Structure	6
4.2 Test groups	7
4.3 Type of SUT test groups	7
4.4 Behaviour test groups.....	7
4.4.1 Valid Behaviour (BV) tests.....	7
4.4.2 Invalid Behaviour (BI) tests.....	7
5 Test Purposes (TP)	7
5.1 Introduction	7
5.1.1 TP definition conventions.....	7
5.1.2 TP naming conventions	8
5.1.3 Sources of TP definitions.....	8
5.2 MAC test purposes for On-Board Unit.....	8
5.2.1 BV test purposes	8
5.2.2 BI test purposes.....	11
5.3 MAC test purposes for Road-Side Unit.....	18
5.3.1 BV test purposes	18
5.3.2 BI test purposes.....	20
5.4 LLC test purposes for On-Board Unit	26
5.4.1 BV test purposes	26
5.4.2 BI test purposes.....	27
5.5 LLC test purposes for Road-Side Unit	29
5.5.1 BV test purposes	29
5.5.2 BI test purposes.....	31
Annex A (informative): Test coverage matrix	33
A.1 Introduction	33
A.2 OBU test coverage matrix	33
A.3 RSU test coverage matrix.....	39
History	45

Intellectual Property Rights

IPRs essential or potentially essential to the present document may have been declared to ETSI. The information pertaining to these essential IPRs, if any, is publicly available for **ETSI members and non-members**, and can be found in ETSI SR 000 314: "*Intellectual Property Rights (IPRs); Essential, or potentially Essential, IPRs notified to ETSI in respect of ETSI standards*", which is available from the ETSI Secretariat. Latest updates are available on the ETSI Web server (<http://webapp.etsi.org/IPR/home.asp>).

Pursuant to the ETSI IPR Policy, no investigation, including IPR searches, has been carried out by ETSI. No guarantee can be given as to the existence of other IPRs not referenced in ETSI SR 000 314 (or the updates on the ETSI Web server) which are, or may be, or may become, essential to the present document.

Foreword

This Technical Specification (TS) has been produced by ETSI Technical Committee Intelligent Transport System(ITS).

The present document is part 1, sub-part 2 of a multi-part deliverable covering Intelligent Transport Systems (ITS); Road Transport and Traffic Telematics (RTTT); Test specifications for Dedicated ShortRange Communication (DSRC) transmission equipment as identified below:

Part 1: "DSRC data link layer: medium access and logical link control;

Sub-part 1: "Protocol Implementation Conformance Statement (PICS) proforma specification";

Sub-part 2: "Test Suite Structure and Test Purposes (TSS&TP)";

Sub-part 3: "Abstract Test Suite (ATS) and partial PIXIT proforma".

Part 2: "DSRC application layer".

1 Scope

The present document contains the Test Suite Structure (TSS) and Test Purposes (TP) to test the Dedicated Short Range Communication (DSRC); Data Link Control (DLC) layer.

The objective of this test specification is to provide a basis for conformance tests for DSRC equipment giving a high probability of inter-operability between different manufacturer's equipment.

The ISO standard for the methodology of conformance testing (ISO/IEC 9646-1 [5] and ISO/IEC 9646-2 [6]) as well as the ETSI rules for conformance testing (ETS 300 406 [4]) are used as a basis for the test methodology.

2 References

References are either specific (identified by date of publication and/or edition number or version number) or non-specific.

- For a specific reference, subsequent revisions do not apply.
- Non-specific reference may be made only to a complete document or a part thereof and only in the following cases:
 - if it is accepted that it will be possible to use all future changes of the referenced document for the purposes of the referring document;
 - for informative references.

Referenced documents which are not found to be publicly available in the expected location might be found at <http://docbox.etsi.org/Reference>.

For online referenced documents, information sufficient to identify and locate the source shall be provided. Preferably, the primary source of the referenced document should be cited, in order to ensure traceability. Furthermore, the reference should, as far as possible, remain valid for the expected life of the document. The reference shall include the method of access to the referenced document and the full network address, with the same punctuation and use of upper case and lower case letters.

NOTE: While any hyperlinks included in this clause were valid at the time of publication ETSI cannot guarantee their long term validity.

2.1 Normative references

The following referenced documents are indispensable for the application of the present document. For dated references, only the edition cited applies. For non-specific references, the latest edition of the referenced document (including any amendments) applies.

- [1] CEN EN 12795 (2003): "Road transport and traffic telematics - Dedicated Short Range Communication (DSRC) - DSRC data link layer: medium access and logical link control".
- [2] CEN EN 12253 (2003): "Road transport and traffic telematics - Dedicated short-range communication - Physical layer using microwave at 5,8 GHz".
- [3] CEN EN 13372 (2003): "Road transport and traffic telematics (RTTT) - Dedicated short-range communication - Profiles for RTTT".
- [4] ETSI ETS 300 406: "Methods for Testing and Specification (MTS); Protocol and profile conformance testing specifications; Standardization methodology".
- [5] ISO/IEC 9646-1 (1991): "Information technology - Open Systems Interconnection - Conformance testing methodology and framework - Part 1: General concepts".

- [6] ISO/IEC 9646-2 (1991): "Information technology - Open Systems Interconnection - Conformance testing methodology and framework - Part 2: Abstract Test Suite specification".
- [7] ISO/IEC 9646-6 (1991): "Information technology - Open Systems Interconnection - Conformance testing methodology and framework - Part 6: Protocol profile test specification".
- [8] ISO/IEC 9646-7 (1991): "Information technology - Open Systems Interconnection - Conformance testing methodology and framework - Part 7: Implementation Conformance Statement".

2.2 Informative references

The following referenced documents are not essential to the use of the present document but they assist the user with regard to a particular subject area. For non-specific references, the latest version of the referenced document (including any amendments) applies.

- [i.1] ETSI TS 102 178: "Broadband Radio Access Networks (BRAN); HiperMAN; Data Link Control (DLC) layer".

3 Definitions and abbreviations

3.1 Definitions

For the purposes of the present document, the terms and definitions given in ISO/IEC 9646-7 [8], EN 12253 [2], EN 12795 [1] and EN 13372 [3] and the following apply:

blocked signal: signal without clock and bit information, e.g. a very weak signal

3.2 Abbreviations

For the purposes of the present document, the abbreviations given in ISO/IEC 9646-1 [5], ISO/IEC 9646-6 [7], ISO/IEC 9646-7 [8], TS 102 178 [i.1] and EN 12795 [1] and the following apply:

DLC	Data Link Control
PrWA	MAC frame Private Window Allocation
PrWRq	MAC frame Private Window Request
U8	Uplink bit rate
U13a	Uplink preamble length (duration)
TSS	Test Suite Structure

4 Test Suite Structure (TSS)

4.1 Structure

Figure 1 shows the DLC Test Suite Structure (TSS) including its subgroups defined for the conformance testing.

Group	Type of SUT	Behaviour
DLC MAC Sub layer	On Board Unit	Valid behaviour
		Invalid behaviour
	Road Side Unit	Valid behaviour
		Invalid behaviour
DLC LLC Sub layer	On Board Unit	Valid behaviour
		Invalid behaviour
	Road Side Unit	Valid behaviour
		Invalid behaviour

Figure 1: TSS for DSRC DLC

4.2 Test groups

The test groups are organized in two groups. The first is designed for the DLC MAC sub layer testing and the second is designed for DLC LLC sub layer testing.

4.3 Type of SUT test groups

The type of SUT test groups are organized in two groups. The first is designed for the On Board Unit testing and the second is designed for Road Side Unit testing.

4.4 Behaviour test groups

4.4.1 Valid Behaviour (BV) tests

This test sub group shall verify that the IUT reacts in conformity with the EN, after receipt or exchange of a valid Protocol Data Units (PDUs). Valid PDUs means that the exchange of messages and the content of the exchanged messages are considered as valid.

4.4.2 Invalid Behaviour (BI) tests

This test sub group shall verify that the IUT reacts in conformity with the EN, after receipt of a syntactically invalid PDU.

5 Test Purposes (TP)

5.1 Introduction

5.1.1 TP definition conventions

The TPs are defined following particular rules as shown in table 1.

Table 1: TP definition rules

TP Id according to the TP naming conventions	Title
	Reference
	PICS Selection
	TC Reference
	Initial condition
	Stimulus and Expected behaviour

TP Id	The TP Id is a unique identifier. It shall be specified according to the TP naming conventions defined in the sub-clause below.
Title	Short description of test purpose objective.
Reference	The reference should contain the references of the subject to be validated by the actual TP (specification reference, clause, paragraph).
PICS Selection	Reference to the PICS statement involved for selection of the TP. Contains a Boolean expression. Only those PICS statements are shown that are explicitly related to the test.
TC reference	Shows the reference number of the related Test Case in the ATS.
Initial condition	The condition defines in which initial state the IUT has to be to apply the actual TP.
Stimulus and Expected behaviour	Definition of the events the tester performs, and the events that are expected from the IUT to conform to the base specification.

5.1.2 TP naming conventions

The identifier of the TP is built according to table 2.

Table 2: TP naming convention

Identifier:	TP/<layer>/<sut>/<x>-<nn>		
	<layer>	MAC	MAC sub-layer
		LLC	LLC sub-layer
	<sut> = type of SUT	OBU	On Board Unit
		RSU	Road Side Unit
	x = Type of testing	BV	Valid Behaviour Tests
		BI	Invalid Behaviour Tests
	<nn> = sequential number	(01-99)	Test Purpose Number

5.1.3 Sources of TP definitions

All TPs are specified according to EN 12795 [1] and EN 13372 [3] with side-information from EN 12253 [2].

5.2 MAC test purposes for On-Board Unit

5.2.1 BV test purposes

Test subgroup objective:

- to test the behaviour of the IUT in relation to syntactically and contextual correct behaviour of the test system.

Test purposes:

TP/MAC/OBU/BV/01	Verify that the OBU can receive downlink frames of maximum allowed length as defined by N2
	Reference: EN 12795 [1], clauses 7.3.3, 7.4.3.1.1 d) and annex A
	PICS Selection: Table A.2/2 AND Table A.5/4 AND Table A.6/7
	TC reference: TC_MAC_OBU_BV_01
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. The number of profiles in the profilelist shall be such, that the number of octets in the frame equals the maximum number as defined by N2. 2. Verify IUT does send a PrWRq within one of the public uplink windows allocated.

TP/MAC/OBU/BV/02	Verify that the OBU can receive a downlink frame following immediately within T1 after the end of an uplink frame transmitted by the same OBU
	Reference: EN 12795 [1], clause 7.3.3 and annex A
	PICS Selection: Table A.2/2 AND Table A.5/4 AND Table A.6/1
	TC reference: TC_MAC_OBU_BV_02
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq in any of the public uplink windows allocated. 3. Tester sends PrWA. 4. Verify IUT sends a VST within the private uplink window allocated. 5. Tester sends ACn command, e.g. DLL ECHO or EFC ECHO, such, that the preamble of the ACn command frame starts exactly T1 after the end of the last bit of the end flag of the VST frame. 6. Verify IUT sends the ACn response.

TP/MAC/OBU/BV/03	Verify that the OBU implements the timing constraints T3, T4b and T5 for public uplink windows
	Reference: EN 12795 [1], clause 7.3.4.2 and annex A
	PICS Selection: Table A.2/2 AND Table A.6/3 AND Table A.6/5 AND Table A.6/6
	TC reference: TC_MAC_OBU_BV_03
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq in one of the public uplink windows allocated. 3. Tester records time: <ul style="list-style-type: none"> • Ts from the end of last bit of the end flag of the BST frame until the beginning of the preamble of the PrWRq frame, and time. • Te from the end of last bit of the end flag of the BST frame until the end of the last bit of the end flag of the PrWRq frame. 4. Verify IUT behaves according to table 3. 5. Repeat the previous steps until the IUT has selected each of the N5 public uplink windows at least once.

Table 3: Timing for public uplink window

Public uplink window number	Start time Ts	End time Te
1	$T3 < Ts < T3 + T4b$	$Te < T3 + T5$
2	$T3 + T5 < Ts < T3 + T5 + T4b$	$Te < T3 + 2 \cdot T5$
...		
N5	$T3 + ((N5-1) \cdot T5) < Ts < T3 + ((N5-1) \cdot T5) + T4b$	$Te < T3 + N5 \cdot T5$

TP/MAC/OBU/BV/04	Verify that the OBU can receive a downlink frame which follows another downlink frame immediately within T2
	Reference: EN 12795 [1], clause 7.3.3 and annex A
	PICS Selection: Table A.2/2 AND Table A.5/4 AND Table A.6/2
	TC reference: TC_MAC_OBU_BV_04
	Initial condition: OBU being not initialized and not in sleep mode
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends a frame with a private LID, not allocating a frame. 2. Within T2, the tester sends downlink frame containing BST, allocating N5 public uplink windows. 3. Verify IUT sends a PrWRq in one of the public uplink windows allocated.

TP/MAC/OBU/BV/05	Verify that the OBU implements the timing constraints T3 and T4a and N3 for private uplink windows
	Reference: EN 12795 [1], clause 7.3.4.1 and annex A EN 12253 [2], clause 5.3
	PICS Selection: Table A.2/2 AND Table A.5/2 AND Table A.6/3 AND Table A.6/4 AND Table A.6/8
	TC reference: TC_MAC_OBU_BV_05
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester performs an initialization cycle BST / PrWRq / PrWA / VST. 2. Tester records time: <ul style="list-style-type: none"> • Ts from the end of the last bit of the end flag of the PrWA frame allocating a private uplink window until the beginning of the preamble of the VST frame in the allocated private uplink window, and time. • Te from the end of the last bit of the end flag of the PrWA frame allocating a private uplink window until the end of the last bit of the end flag of the VST frame in the allocated private uplink window. 3. Verify IUT behaves according to table 4.

Table 4: Timing for private uplink window

Start time T_s	End time T_e
$T_3 < T_s < T_3 + T_{4a}$	$T_e < T_3 + T_{4a} + U_{13a} + (8 \cdot N_3 + \text{stuff bits}) / U_8$

TP/MAC/OBU/BV/06	Verify that the OBU correctly manages the S-bit and L-Bit in the MAC control field for the purpose of possible re-transmission of VST frames
	Reference: EN 12795 [1], clauses 7.3.2.1, 7.4.3.1.3 and 7.4.3.1.4
	PICS Selection: Table A.2/2 AND Table A.4/6 AND Table A.7/2 AND Table A.7/3
	TC reference: TC_MAC_OBU_BV_06
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq in one of the public uplink windows allocated. 3. Tester sends PrWA and records the value of the S-bit used. 4. Tester ignores a possible reception of a VST in the allocated private uplink window. 5. Tester sends PrWA with the S-bit set to the same value as in step 3. 6. Verify IUT sends the VST.
TP/MAC/OBU/BV/07	Verify that the OBU correctly manages the local S-bit state variable based on the S-bit and L-Bit in the received MAC control field, where an LPDU is present in the allocating downlink frame.
	Reference: EN 12795 [1], clauses 7.3.2.1, 7.4.3.1.3 and 7.4.3.1.4
	PICS Selection: Table A.2/2 AND Table A.4/6 AND Table A.7/2 AND Table A.7/3 AND Table A.7/4
	TC reference: TC_MAC_OBU_BV_07
	Initial condition: OBU being fully initialized and not in sleep mode.
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends the EFC ECHO ACn command with ECHO_DATA1 and notes the value of the S-bit. 2. Verify IUT sends the EFC ECHO response with ECHO_DATA1. 3. Tester sends the EFC ECHO ACn command with ECHO_DATA2. The S-bit shall be set to the same value as used in step 1. 4. Verify IUT sends the EFC ECHO response with ECHO_DATA2. 5. Tester sends PrWA with the S-bit set to the same value as in step 3. 6. Verify IUT sends the EFC ECHO response with ECHO_DATA2.
TP/MAC/OBU/BV/08	Verify that the OBU randomly selects one of the N5 public uplink windows.
	Reference: EN 12795 [1], clause 7.3.4.3
	PICS Selection: Table A.2/2 AND Table A.5/1
	TC reference: TC_MAC_OBU_BV_08
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 = three public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester records number of public uplink window selected. 4. Tester repeats steps 1. to 3. X times with X = 100. 5. Verify IUT selects all possible public uplink windows at least 0,3·X times.
NOTE: In case the test fails, increase value of X and repeat test.	

TP/MAC/OBU/BV/09	Verify that the OBU can detect and manage both valid values of the C/R-bit in the MAC control field of a PrWA frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.4/6 <i>Note: Test does not apply for profiles 0/1 of EN 13372 [3]</i>
	TC reference: TC_MAC_OBU_BV_09
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends PrWRq in the allocated private uplink window. 3. Tester sends PrWA frame with the C/R-bit of the MAC control field set to 1. 4. Verify IUT sends VST in the allocated private uplink window. 5. Tester sends PrWA frame with the C/R-bit of the MAC control field set to 0. The S-bit shall have the same value as in step 3. 6. Verify IUT sends VST in the allocated private uplink window.

5.2.2 BI test purposes

Test subgroup objective:

- to check the behaviour of the of the IUT in response to invalid messages and behaviour from the test tool.

Test purposes:

TP/MAC/OBU/BI/01	Verify that the OBU can detect and manage double-bit errors in the LID field, MAC control field and LPDU field of the downlink frame using the FCS field
	Reference: EN 12795 [1], clauses 5.5 and 7.4.3.1.1 e)
	PICS Selection: Table A.2/2 AND Table A.4/8 AND Table A.7/1 AND Table A.7/6
	TC reference: TC_MAC_OBU_BI_01
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but introduces a random double-bit error in the frame on transmission. The bit error shall be introduced between the end of the start flag and the start of the FCS field. 2. Verify IUT does not respond within any of the public uplink windows allocated. 3. Repeat test in case the errors produced a flag or an abort sequence.

TP/MAC/OBU/BI/02	Verify that the OBU can detect and manage double-bit errors in the FCS field of the downlink frame using the FCS field
	Reference: EN 12795 [1], clauses 5.5 and 7.4.3.1.1 e)
	PICS Selection: Table A.2/2 AND Table A.4/8 AND Table A.7/1 AND Table A.7/6
	TC reference: TC_MAC_OBU_BI_02
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but introduces a random double-bit error in the FCS field on transmission. 2. Verify IUT does not respond within any of the public uplink windows allocated. 3. Repeat test in case the errors produced a flag or an abort sequence.

TP/MAC/OBU/BI/03	Verify that the OBU can detect and manage a block of 15 bit errors in the downlink frame using the FCS field
	Reference: EN 12795 [1], clauses 5.5 and 7.4.3.1.1 e)
	PICS Selection: Table A.2/2 AND Table A.4/8 AND Table A.7/1 AND Table A.7/6
	TC reference: TC_MAC_OBU_BI_03
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but introduces a block of 15 subsequent bit errors randomly located in the frame on transmission. The block of bit errors shall be introduced between the end of the start flag and the start of the end flag. 2. Verify IUT does not respond within any of the public uplink windows allocated. 3. Repeat test in case the errors produced a flag or an abort sequence. 	
TP/MAC/OBU/BI/04	Verify that the OBU can detect and manage the abort sequence in the LPDU field of a downlink frame
	Reference: EN 12795 [1], clauses 5.7 and 7.4.3.1.1
	PICS Selection: Table A.2/2 AND Table A.7/1
	TC reference: TC_MAC_OBU_BI_04
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST modified such, that the beaconId contains a sequence of seven consecutive one bits, allocating N5 public uplink windows. The zero-bit insertion shall not be applied to the beaconId field. The FCS shall be correct with respect to the actually transmitted frame. 2. Verify IUT does not respond within any of the public uplink windows allocated. 	
TP/MAC/OBU/BI/05	Verify that the OBU can detect and manage the abort sequence at the end of a downlink frame
	Reference: EN 12795 [1], clauses 5.7 and 7.4.3.1.1
	PICS Selection: Table A.2/2 AND Table A.7/1
	TC reference: TC_MAC_OBU_BI_05
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST modified such, that the end flag is replaced by the abort sequence, allocating N5 public uplink windows. The FCS shall be correct. 2. Verify IUT does not respond within any of the public uplink windows allocated. 	
TP/MAC/OBU/BI/06	Verify that the OBU can detect and manage a downlink frame being too long according to N2
	Reference: EN 12795 [1], clauses 7.3.3, 7.4.3.1.1 d) and annex A
	PICS Selection: Table A.2/2 AND Table A.5/4 AND Table A.7/1 AND Table A.6/7
	TC reference: TC_MAC_OBU_BI_06
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. The number of profiles in the profilelist shall be such, that the number of octets in the frame just exceeds by one the maximum number of octets allowed as defined by N2. 2. Verify IUT does not respond within any of the public uplink windows allocated. 	

TP/MAC/OBU/BI/07	Verify that the OBU can detect and manage wrong format of private LID in a downlink frame
	Reference: EN 12795 [1], clauses 5.2.1, 7.4.3.1.1 b) and 7.4.3.1.3
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/3
	TC reference: TC_MAC_OBU_BI_07
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated using private LID = LID1 3. Tester sends PrWA with private LID = LID1, but contained in five octets. 4. Verify IUT does not send VST in the allocated private uplink window. 	
TP/MAC/OBU/BI/08	Verify that the OBU can detect and manage a missing MAC control field in a downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/1
	TC reference: TC_MAC_OBU_BI_08
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester sends PrWA, but without a MAC control field in it. 4. Verify IUT does not send VST in the allocated private uplink window. 	
TP/MAC/OBU/BI/09	Verify that the OBU can detect and manage a wrong A-bit in the MAC control field in a broadcast downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_09
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, but the A-bit of the MAC control field set to 0. 2. Verify IUT does not send PrWRq within the time normally used for the N5 subsequent public uplink windows. 	
TP/MAC/OBU/BI/10	Verify that the OBU can detect and manage a wrong D-bit in the MAC control field in a broadcast downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_10
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but the D-bit of the MAC control field set to 1. 2. Verify IUT does not send PrWRq in the allocated private uplink window. 	

TP/MAC/OBU/BI/11	Verify that the OBU can detect and manage a wrong D-bit in the MAC control field in a private downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_11
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester sends PrWA, but the D-bit of the MAC control field set to 1. 4. Verify IUT does not send VST in the allocated private uplink window.
TP/MAC/OBU/BI/12	Verify that the OBU can detect and manage a wrong L-bit in the MAC control field in a broadcast downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_12
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but the L-bit of the MAC control field set to 0. 2. Verify IUT does not send PrWRq in the allocated private uplink window.
TP/MAC/OBU/BI/13	Verify that the OBU can detect and manage a wrong L-bit in the MAC control field in a private downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_13
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester sends PrWA, but the L-bit of the MAC control field set to 1. 4. Verify IUT does not send VST in the allocated private uplink window.
TP/MAC/OBU/BI/14	Verify that the OBU can detect and manage a wrong C/R-bit in the MAC control field of a PrWa frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c) EN 13372 [3], clause 6.4.2
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6 AND Table E.1/1 AND Table E.2/1 AND Table E.2/4 and Table E.2/5 <i>Note: Test applies only for profiles 0/1 of EN 13372 [3]</i>
	TC reference: TC_MAC_OBU_BI_14
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends PrWRq in the allocated private uplink window. 3. Tester sends PrWA frame with the C/R-bit of the MAC control field set to 1. 4. Verify IUT does not sent VAT in the allocated private uplink window. 5. Tester sends PrWA frame. 6. Verify IUT sends VST in the allocated private uplink window.

TP/MAC/OBU/BI/15	Verify that the OBU can detect and manage a wrong MAC control field in a downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_15
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester sends PrWA, but with all X bits in the MAC control field set to 1. 4. Verify IUT does not send VST in the allocated private uplink window. 	
TP/MAC/OBU/BI/16	Verify that the OBU can detect and manage blocked signals in a downlink frame
	Reference: EN 12795 [1], clauses 5.1, 5.7 and 7.4.3.1.1 e)
	PICS Selection: Table A.2/2 AND Table A.5/4 AND Table A.7/1 AND Table A.7/6
	TC reference: TC_MAC_OBU_BI_16
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but the radio signal is blocked for 15 consecutive bit periods in the frame on transmission. The blocked bits shall be between the end of the start flag and the start of the end flag. 2. Verify IUT does not respond within any of the public uplink windows allocated. 	
TP/MAC/OBU/BI/17	Verify that the OBU can detect and manage a blocked end flag in a downlink frame
	Reference: EN 12795 [1], clause 7.4.3.1.1 a)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.7/6
	TC reference: TC_MAC_OBU_BI_17
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but the radio signal is blocked during transmission of the end flag in the frame. 2. Verify IUT does not respond within any of the public uplink windows allocated. 	
TP/MAC/OBU/BI/18	Verify that the OBU can detect and manage a blocked start flag in a downlink frame
	Reference: EN 12795 [1], clause 7.4.3.1.1 a)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.7/6
	TC reference: TC_MAC_OBU_BI_18
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows, but the radio signal is blocked for the start flag in the frame on transmission. 2. Verify IUT does not respond within any of the public uplink windows allocated. 	

TP/MAC/OBU/BI/19	Verify that the OBU can detect and manage a broadcast LID where a private LID should be used in a downlink frame
	Reference: EN 12795 [1], clauses 5.2.1, 5.2.2, 7.4.3.1.1 b) and 7.4.3.1.3
	PICS Selection: Table A.2/2 AND Table A.4/3 AND Table A.4/4 AND Table A.7/1
	TC reference: TC_MAC_OBU_BI_19
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated using private LID = LID1. 3. Tester sends PrWA, but using broadcast LID instead of LID1. 4. Verify IUT does not send VST in the allocated public uplink windows. 5. Tester sends PrWA with private LID=LID1 and the MAC S-Bit set to S=0. 6. Verify IUT sends VST in the allocated private uplink window.

TP/MAC/OBU/BI/20	Verify that the OBU can detect and manage a multicast LID where a private LID should be used in a downlink frame
	Reference: EN 12795 [1], clauses 5.2.1, 5.2.3, 7.4.3.1.1 b) and 7.4.3.1.3
	PICS Selection: Table A.2/2 AND Table A.4/3 AND Table A.4/5 Table A.7/1 Table A.7/5
	TC reference: TC_MAC_OBU_BI_20
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated using private LID = LID1. The seven least significant bits of LID1 shall not be all 1. 3. Tester sends MAC frame with A-Bit set to 1 and with multicast address such that the link address field equals the least significant octet of link address field for LID1. 4. Verify IUT does not send VST in the allocated uplink window. 5. Tester sends PrWA with private LID=LID1 and the MAC S-Bit set to S=0. 6. Verify IUT sends VST in the allocated private uplink window.
NOTE: In the event of the OBU under test has implemented a multicast address, this multicast address shall not be used for the test.	

TP/MAC/OBU/BI/21	Verify that the OBU can detect and manage a wrong A-bit in the MAC control field in a private downlink frame
	Reference: EN 12795 [1], clauses 7.3.2.1 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6 AND Table A.7/2
	TC reference: TC_MAC_OBU_BI_21
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester sends PrWA, but the A-bit of the MAC control field set to 0. 4. Verify IUT does not send VST within the time expected for a private uplink window. 5. Tester sends PrWA. 6. Verify IUT sends VST in the allocated private uplink window.

TP/MAC/OBU/BI/22	Verify that the OBU can manage a wrong A-bit in the MAC control field in a private downlink frame containing an ACn command
	Reference: EN 12795 [1], clauses 7.3.2.1, 7.4.3.2.2 and 7.4.3.1.1 c)
	PICS Selection: Table A.2/2 AND Table A.7/1 AND Table A.4/6
	TC reference: TC_MAC_OBU_BI_22
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated. 3. Tester sends PrWA. 4. Verify IUT sends VST within the time expected for a private uplink window. 5. Tester sends ACn command that requires a response from the application layer, e.g. ECHO command, and with MAC A-bit set to zero. 6. Verify IUT does not send the ACn response immediately following the command within the time normally used for a private uplink window.
TP/MAC/OBU/BI/23	Verify that the OBU can detect and manage wrong private LID in a downlink frame
	Reference: EN 12795 [1], clauses 5.2.1, 7.4.3.1.1 b) and 7.4.3.1.3
	PICS Selection: Table A.2/2 AND Table A.4/3 AND Table A.7/5 AND Table A.7/1
	TC reference: TC_MAC_OBU_BI_23
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated using private LID = LID1. 3. Tester sends PrWA with private LID different to LID1, but with correct format. 4. Verify IUT does not send VST in the allocated private uplink window. 5. Tester sends PrWA with private LID = LID1. 6. Verify IUT sends VST in the allocated private uplink window.
TP/MAC/OBU/BI/24	Verify that the OBU can manage retransmission of PrWRq
	Reference: EN 12795 [1], clause 7.4.3.2.2
	PICS Selection: Table A.7/5
	TC reference: TC_MAC_OBU_BI_24
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends downlink frame containing BST, allocating N5 public uplink windows. 2. Verify IUT sends a PrWRq within one of the public uplink windows allocated using private LID = LID1. 3. Tester ignores PrWRq and repeats step 1. 4. Verify IUT repeats step 2.

5.3 MAC test purposes for Road-Side Unit

5.3.1 BV test purposes

Test subgroup objective:

- to test the behaviour of the IUT in relation to syntactically and contextual correct behaviour of the test system.

Test purposes:

TP/MAC/RSU/BV/01	Verify that the RSU can receive uplink frames of maximum allowed length in private uplink windows defined by N3.
	Reference: EN 12795 [1], clauses 7.3.4.1, 7.4.2.1.1 e) and annex A
	PICS Selection: Table B.2/2 AND Table B.5/2 AND Table B.6/8
	TC reference: TC_MAC_RSU_BV_01
	Initial condition: RSU is running any application, and is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT allocates a private uplink window. 3. Tester sends VST in the allocated private uplink window. The length of the applicationList shall be such that the number of octets in the frame equals the maximum number as defined by N3. 4. Verify IUT sends a privately addressed frame in order to acknowledge reception of the VST.

TP/MAC/RSU/BV/02	Verify that the RSU implements the timing constraint T1
	Reference: EN 12795 [1], clauses 7.3.3 and annex A
	PICS Selection: Table B.2/2 AND Table B.5/1 AND Table B.6/1
	TC reference: TC_MAC_RSU_BV_02
	Initial condition: RSU is running any application, and is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester and IUT perform a complete initialization cycle including the privately addressed acknowledge frame following BST. Tester records time <ul style="list-style-type: none"> • T from the end of the last bit of the end flag in an uplink window (=PrWRq frame) until the beginning of the preamble of the frame in the subsequent downlink window. In case of public uplink windows, the number of the selected window is considered to calculate the proper window timing. • for the whole application cycle, where applicable. 2. Verify IUT complies with the requirement for T1 always.

TP/MAC/RSU/BV/03	Verify that the RSU implements the correct private medium response time N12 for re-allocations of private uplink windows
	Reference: EN 12795 [1], clause 7.4.2.2.3 and annex A
	PICS Selection: Table B.2/2 AND Table B.7/5
	TC reference: TC_MAC_RSU_BV_03
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. The repetition rate for BST transmissions shall be set such, that in between subsequent BST transmissions several PrWA frames are possible. No LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester send PrWRq in one of the allocated public uplink windows. 2. Verify the IUT sends PrWA. 3. Tester ignores all possible receptions of PrWA frames and reception of all subsequent BST frames. 4. Verify IUT repeats PrWA only until it transmits the next BST.

TP/MAC/RSU/BV/04	Verify that the RSU implements the correct S-bit mechanism for re-allocations of private uplink windows and performs correct initialization of the S-bit.
	Reference: EN 12795 [1], clauses 7.4.2.2.2, 7.4.2.2.3 and annex A
	PICS Selection: Table B.2/2 AND Table B.7/4 and Table B.7/5
	TC reference: TC_MAC_RSU_BV_04
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. The repetition rate for BST transmissions shall be set such, that in between subsequent BST transmissions several PrWA frames are possible. No LID is registered
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWRq with LID=LID1 in one of the allocated public uplink windows. 2. Verify the IUT sends PrWA. 3. Tester records the value of the S-bit received and ignores all possible receptions of PrWA frames. 4. Verify IUT only uses S=0. 	
TP/MAC/RSU/BV/05	Verify that the RSU can detect and manage the unusual value of the C/R-bit in the MAC control field of a PrWRq frame
	Reference: EN 12795 [1], clauses 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 AND Table B.7/1 <i>Note Test does not apply for profiles 0/1 of EN 13372 [3]</i>
	TC reference: TC_MAC_RSU_BV_05
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered.
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWR in one of the N5 public uplink windows with the C/R-bit of the MAC control field set to 1 (=response). 2. Verify IUT sends PrWA. 	
TP/MAC/RSU/BV/06	Verify that the RSU can receive in all N5 public uplink windows
	Reference: EN 12795 [1], clauses 7.3.4
	PICS Selection: Table B.5/3 and Table B.6/10
	TC reference: TC_MAC_RSU_BV_06, TC_MAC_RSU_BV_07, TC_MAC_RSU_BV_08
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered.
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWR in the first of the N5 public uplink windows. 2. Verify IUT sends PrWA. 3. Tester ignores PrWA from step 2, and ignores all further downlink frames except BST. 4. Repeat steps 1. through 3. for all other public uplink windows. 	
TP/MAC/RSU/BV/07	Verify that the RSU correctly manages private uplink window request
	Reference: EN 12795 [1], clauses 7.4.2.1.3
	PICS Selection: Table B.5/3 and Table B.7/4
	TC reference: implicitly tested
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered.
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the N5 public uplink windows. 2. Verify IUT sends PrWA before the next BST. 	

TP/MAC/RSU/BV/08	Verify that the RSU correctly manages private uplink window allocation in downlink frames requesting an immediate response
	Reference: EN 12795 [1], clauses 7.4.2.2.2
	PICS Selection: Table B.7/4
	TC reference: implicitly tested
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered. RSU is serving an application that requires transmission of an ACn command as first command.
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the N5 public uplink windows. 2. Upon reception of PrWA tester send VST. 3. Verify IUT sends an ACn command with the A-bit set to one allocating a private uplink window.

5.3.2 BI test purposes

Test subgroup objective:

- to check the behaviour of the of the IUT in response to invalid messages and behaviour from the test tool.

Test purposes:

TP/MAC/RSU/BI/01	Verify that the RSU can detect and manage double-bit errors in the in the information field of the LPDU of the uplink frame using the FCS field
	Reference: EN 12795 [1], clauses 5.5 and 7.4.2.1.1 f)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.7/7
	TC reference: TC_MAC_RSU_BI_01
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT responds with PrWA. 3. Tester sends VST but introduces a random double-bit error in the frame on transmission. The bit error shall be introduced in the information field of the LPDU. 4. Verify IUT does not respond with a privately addressed frame. 5. Repeat test in case the errors produced a flag or an abort sequence.

TP/MAC/RSU/BI/02	Verify that the RSU can detect and manage double-bit errors in the FCS field of the uplink frame using the FCS field
	Reference: EN 12795 [1], clauses 5.5 and 7.4.2.1.1 f)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.7/7
	TC reference: TC_MAC_RSU_BI_02
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but introduces a random double-bit error in FCS field on transmission. 2. Verify IUT does not respond within PrWA. 3. Repeat test in case the errors produced a flag or an abort sequence.

TP/MAC/RSU/BI/03	Verify that the RSU can detect and manage a block of 15 bit errors in the uplink frame using the FCS field
	Reference: EN 12795 [1], clauses 5.5 and 7.4.2.1.1 f)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.7/7
	TC reference: TC_MAC_RSU_BI_03
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST in the allocated private uplink window, but introduces a block of 15 subsequent bit errors randomly located in the frame on transmission. The block of bit errors shall be introduced in the information field of the LPDU. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1. 5. Repeat test in case the errors produced a flag or an abort sequence.
TP/MAC/RSU/BI/04	Verify that the RSU can detect and manage the abort sequence in the LPDU field of an uplink frame
	Reference: EN 12795 [1], clauses 5.7 and 7.4.2.1.1 a)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.7/8
	TC reference: TC_MAC_RSU_BI_04
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST in the allocated private uplink window such, that the ObeConfiguration contains a sequence of seven consecutive one bits. The zero-bit insertion shall not be applied to the obeConfiguration field. The FCS shall be correct with respect to the actually transmitted frame. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.
TP/MAC/RSU/BI/05	Verify that the RSU can detect and manage the abort sequence at the end of an uplink frame
	Reference: EN 12795 [1], clauses 5.7 and 7.4.2.1.1 a)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.7/8
	TC reference: TC_MAC_RSU_BI_05
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows modified such, that the end flag is replaced by the abort sequence (last bit of end flag set to "1"). The FCS shall be correct. 2. Verify IUT does not respond within PrWA.

TP/MAC/RSU/BI/06	Verify that the RSU can detect and manage a frame in a private uplink window being too long according to N3
	Reference: EN 12795 [1], clauses 7.3.4.1, 7.4.2.1.1 e) and annex A
	PICS Selection: Table B.2/2 AND Table B.5/2 AND Table B.6/8 AND Table B.7/1
	TC reference: TC_MAC_RSU_BI_06
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST, The length of applicationList shall be such that the number of octets in the frame just exceeds by one the maximum number of octets allowed as defined by N3. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.
TP/MAC/RSU/BI/07	Verify that the RSU can detect and manage wrong private LID in an uplink frame
	Reference: EN 12795 [1], clauses 5.2.1, 7.4.2.1.1 c) and 7.4.2.2.2
	PICS Selection: Table B.2/2 AND Table B.4/3 AND Table B.7/1
	TC reference: TC_MAC_RSU_BI_07
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST, but uses a new private LID. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.
TP/MAC/RSU/BI/08	Verify that the RSU can detect and manage wrong format of private LID in an uplink frame
	Reference: EN 12795 [1], clauses 5.2.1, 7.4.2.1.1 c) and 7.4.2.2.2
	PICS Selection: Table B.2/2 AND Table B.4/3 AND Table B.7/1
	TC reference: TC_MAC_RSU_BI_08
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST, but private LID contained in five octets. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.
TP/MAC/RSU/BI/09	Verify that the RSU can detect and manage broadcast LID in case private LID is to be used in an uplink frame
	Reference: EN 12795 [1], clauses 5.2.2, 7.4.2.1.1 c) and 7.4.2.2.2
	PICS Selection: Table B.2/2 AND Table B.4/3 AND Table B.7/1
	TC reference: TC_MAC_RSU_BI_09
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST, but with broadcast address instead of private LID. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.

TP/MAC/RSU/BI/10	Verify that the RSU can detect and manage multicast LID in case private LID is to be used in an uplink frame
	Reference: EN 12795 [1], clauses 5.2.3, 7.4.2.1.1 c) and 7.4.2.2.2
	PICS Selection: Table B.2/2 AND Table B.4/3 AND Table B.7/1 AND Table B.7/4
	TC reference: TC_MAC_RSU_BI_10
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST, but with multicast address instead of private LID. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1. 	
TP/MAC/RSU/BI/11	Verify that the RSU can detect and manage a missing MAC control field in an uplink frame
	Reference: EN 12795 [1], clauses 5.3, 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/1 AND Table B.7/1
	TC reference: TC_MAC_RSU_BI_11
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but without a MAC control field in it. 2. Verify IUT does not send PrWA. 	
TP/MAC/RSU/BI/12	Verify that the RSU can detect and manage a wrong D-bit in the MAC control field in a frame in a public uplink window
	Reference: EN 12795 [1], clauses 5.3, 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 and B.7/1
	TC reference: TC_MAC_RSU_BI_12
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but the D-bit of the MAC control field set to 0. 2. Verify IUT does not send PrWA. 	
TP/MAC/RSU/BI/13	Verify that the RSU can detect and manage a wrong D-bit in the MAC control field in a frame in a private uplink window
	Reference: EN 12795 [1], clauses 5.3, 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 and B.7/1
	TC reference: TC_MAC_RSU_BI_13
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST in the allocated private uplink window, but the D-bit of the MAC control field set to 0. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1. 	

TP/MAC/RSU/BI/14	Verify that the RSU can detect and manage a wrong L-bit in the MAC control field in a frame in a public uplink window
	Reference: EN 12795 [1], clauses 5.3, 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 and B.7/1
	TC reference: TC_MAC_RSU_BI_14
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but the L-bit of the MAC control field set to 1. 2. Verify IUT does not send PrWA.
TP/MAC/RSU/BI/15	Verify that the RSU can detect and manage a wrong L-bit in the MAC control field in a frame in a private uplink window
	Reference: EN 12795 [1], clauses 5.3, 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 and B.7/1
	TC reference: TC_MAC_RSU_BI_15
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST in the allocated private uplink window, but the L-bit of the MAC control field set to 0. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.
TP/MAC/RSU/BI/16	Verify that the RSU can detect and manage a wrong MAC control field in a frame in a public uplink window
	Reference: EN 12795 [1], clauses 5.3, 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 and B.7/1
	TC reference: TC_MAC_RSU_BI_16
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but with all X bits in the MAC control field set to 1. 2. Verify IUT does not send PrWA.
TP/MAC/RSU/BI/17	Verify that the RSU can detect and manage blocked signals in an uplink frame
	Reference: EN 12795 [1], clause 5.1, 5.7 and 7.4.2.1.1 f)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.7/7
	TC reference: TC_MAC_RSU_BI_17
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT sends PrWA. 3. Tester sends VST in the allocated private uplink window, but blocks 15 consecutive bit periods in the frame on transmission. The blocked bits shall be introduced in the information field of the LPDU. 4. Verify IUT does not acknowledge reception of the VST by sending a privately addressed frame with the MAC L-bit set to 1.

TP/MAC/RSU/BI/18	Verify that the RSU can detect and manage a blocked end flag in an uplink frame
	Reference: EN 12795 [1], clause 5.1, 7.4.2.1.1 a)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.4/2
	TC reference: TC_MAC_RSU_BI_18
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but blocks the end flag in the frame on transmission. 2. Verify IUT does not respond with PrWA.
TP/MAC/RSU/BI/19	Verify that the RSU can detect and manage a blocked start flag in an uplink frame
	Reference: EN 12795 [1] clause 5.1, 7.4.2.1.1 a)
	PICS Selection: Table B.2/2 AND Table B.7/1 AND Table B.4/2
	TC reference: TC_MAC_RSU_BI_19
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but blocks the start flag in the frame on transmission. 2. Verify IUT does not respond with PrWA.
TP/MAC/RSU/BI/20	Verify that the RSU can detect and manage a wrong R-bit in the MAC control field in a frame in a public uplink window
	Reference: EN 12795 [1], clauses 7.3.2.2 and 7.4.2.1.1 d)
	PICS Selection: Table B.2/2 AND Table B.4/7 and Table B.7/1
	TC reference: TC_MAC_RSU_BI_20
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows, but the R-bit of the MAC control field set to 0. 2. Verify IUT does not send PrWA.
TP/MAC/RSU/BI/21	Verify that the RSU can detect and manage an illegal number of octets (>N4) in a frame in a public uplink window
	Reference: EN 12795 [1], clauses 7.3.4.2 and 7.4.2.1.1 e)
	PICS Selection: Table B.2/2 AND Table B.4/7 and Table B.7/1
	TC reference: TC_MAC_RSU_BI_21
	Initial condition: RSU is periodically inviting for initialization, i.e. sending BST with subsequent allocation of N5 public uplink windows. No private LID is registered
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Tester sends PrWRq in one of the allocated public uplink windows. 2. Verify IUT allocates a private uplink window. 3. Tester ignores all receptions of PrWA. 4. Verify IUT sends a further BST with subsequent allocation of N5 public uplink windows. 5. Without changing private LID, tester sends VST in the first public uplink window allocated. 6. Verify IUT does not acknowledge VST by sending a privately addressed frame.

5.4 LLC test purposes for On-Board Unit

5.4.1 BV test purposes

Test subgroup objective:

- to test the behaviour of the IUT in relation to syntactically and contextual correct behaviour of the test system.

Test purposes:

TP/LLC/OBU/BV/01	Verify that the OBU can exchange UI commands.
	Reference: EN 12795 [1], clause 8.4.2
	PICS Selection: Table A2/2 AND Table A.10/1 AND Table A.11/1
	TC reference: TC_LLC_OBU_BV_01
	Initial condition: OBU not in sleep mode and not yet initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends an UI command containing a BST. 2. Verify IUT replies with an UI command containing a VST, with the poll bit in the LLC control field set to P=0. 	
TP/LLC/OBU/BV/02	Verify that the OBU can manage ACn data transmission.
	Reference: EN 12795 [1], clause 8.4.3.5
	PICS Selection: Table A.8/2 AND Table A.13/2 AND Table A.14/1 AND Table A.14/3 AND Table A.14/5 AND Table A.14/7 AND Table A.15/1
	TC reference: TC_LLC_OBU_BV_02
	Initial condition: OBU initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends an AC0 command with Poll bit set to 0. 2. Verify IUT replies with an AC1 response with Final bit set to 0 and status subfield equal to NR_OK. 3. Tester sends an AC1 command with Poll bit set to 0. 4. Verify IUT replies with an AC0 response with Final bit set to 0 and status subfield equal to NR_OK. 	
TP/LLC/OBU/BV/03	Verify that the OBU can manage ACn data exchange.
	Reference: EN 12795 [1], clause 8.4.3.5
	PICS Selection: Table A.8/2 AND Table A.13/3 AND Table A.14/2 AND Table A.14/4 AND Table A.14/6 AND Table A.14/8 AND Table A.15/1
	TC reference: TC_LLC_OBU_BV_03
	Initial condition: OBU initialized, prepared to allow for retrieval of data without causing late response
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends an AC0 command with poll bit set to P=1 requesting retrieval of data from the IUT. 2. Verify IUT provides the requested data in the LSDU subfield of an AC1 response, with final bit set to F=1 and with the status subfield indicating OK_OK. 3. Tester sends an AC1 command with poll bit set to P=1 requesting retrieval of data from the IUT. 4. Verify IUT provides the requested data in the LSDU subfield of an AC0 response, with final bit set to F=1 and with the status subfield indicating OK_OK. 	
TP/LLC/OBU/BV/04	Verify that the OBU can manage correctly a Data Link Echo command.
	Reference: EN 12795 [1], clauses 8.4.3.2 and 8.4.3.3
	PICS Selection: Table A.8/2 AND Table A.13/1 AND (Table A.14/1 OR Table A.14/3) AND (Table A.14/5 OR) Table A.14/7 AND Table A.15/3
	TC reference: TC_LLC_OBU_BV_04
	Initial condition: OBU initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends a Data Link Echo. 2. Verify IUT replies to the Data Link Echo received with the F bit set to F=0, the status subfield set to NR_OK and the LSDU subfield being empty 	

TP/LLC/OBU/BV/05	Verify that the OBU can manage late response Procedure I
	Reference: EN 13372 [3], clause 7.2
	PICS Selection: Table E.4/1
	TC reference: TC_LLC_OBU_BV_05
	Initial condition: OBU already initialized, waiting to be served by tester
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends application layer request for data retrieval from the OBU that causes late response. 2. Verify IUT sends ACn response frame with LLC status subfield containing the value NE_OK, but not providing the requested data. 3. Tester waits for at least the time needed to make the requested data available at the IUT. 4. The MAC of the tester re-transmits the request from step 1. 5. Observe whether IUT provides the data requested in step 1 in the response frame related to step 4. If it does, go to step 8. 6. Tester sends INITIALizaTION.request (BST) with FlowControl=2, granting immediately a private uplink window, if requested. 7. Verify IUT provides the data requested in step 1 using a UI command. <p>If in step 5 the IUT does not provide the data requested, proceed as follows.</p> <ol style="list-style-type: none"> 1. Tester invites for initialization using a new BeaconID and processes correctly all requests from the IUT until reception of VST. 2. As first command after reception of VST, tester sends application layer request for data retrieval from the OBU that causes late response. 3. Verify IUT sends ACn response frame with LLC status subfield containing the value NE_OK, but not providing the requested data. 4. Tester waits for at least the time needed to make the requested data available at the IUT. 5. Tester sends INITIALizaTION.request (BST) granting immediately a private uplink window, if requested. 6. Verify IUT provides the data requested in step 9 using a UI command.
NOTE: Problems at the application caused by possible double reception of the requested data, see step 8, are not considered in this test, as such problems are outside the scope of DSRC.	

5.4.2 BI test purposes

Test subgroup objective:

- to check the behaviour of the of the IUT in response to invalid messages and behaviour from the test tool.

Test purposes:

TP/LLC/OBU/BI/01	Verify that the OBU can correctly detect and manage corrupted LLC control field when a UI command is expected.
	Reference: EN 12795 [1], clauses 8.4.2.1 and 8.3.2.2
	PICS Selection: Table A.2/2 AND A.8/1 AND Table A.9/1 AND Table A.11/1
	TC reference: TC_LLC_OBU_BI_01
	Initial condition: OBU not in sleep mode and not yet initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends an UI command containing a BST, with the two least significant bits in the LLC control field being set to zero. 2. Verify IUT ignores the received LPDU. 3. Repeat steps 1. and 2. for all invalid values of the reserved bits in the LLC control field, with new beaconID in each trial. 4. Tester sends a valid UI command containing a BST with new beaconID. 5. Verify IUT is not blocked by the previous erroneous commands, but replies correctly with VST.

TP/LLC/OBU/BI/02	Verify that the OBU can detect and manage an invalid LPDU, containing a fractional number of octets in length.
	Reference: EN 12795 [1], clause 8.3.5
	PICS Selection: Table A.2/2 AND Table A.8/2 AND Table A.13/3
	TC reference: TC_LLC_OBU_BI_02
	Initial condition: OBU initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends an ACn command (ECHO.request) with an invalid length of the LPDU that is not an integer multiple of one octet. 2. Verify IUT ignores the received LPDU. 	
TP/LLC/OBU/BI/03	Verify that the OBU can correctly detect and manage corrupted LLC control fields when an ACn command is expected.
	Reference: EN 12795 [1], clause 8.3.5
	PICS Selection: Table A.2/2 AND Table A.8/2 Table A.9/1 AND Table A.13/3
	TC reference: TC_LLC_OBU_BI_03
	Initial condition: OBU initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends an ACn command (ECHO.request) with Poll bit set to P=1, but with invalid modifier bits in the LLC control field such, that the LLC control field does not indicate a UI command. 2. Verify IUT ignores the received LPDU. 3. Repeat steps 1. and 2. for all invalid values of the modifier bits. 4. Repeat steps 1. and 2. for all invalid combinations of the reserved bits and with correct setting of the modifier bits. 5. Tester sends a valid ACn command (ECHO.request) with Poll bit set to P=1. 6. Verify IUT is not blocked by the previous erroneous commands, but replies correctly with ACn response (ECHO.response). 	
TP/LLC/OBU/BI/04	Verify that the OBU can detect and manage an LPDU, containing an acknowledged connectionless LLC command control field when the LID is multicast or broadcast.
	Reference: EN 12795 [1], clause 8.3.5
	PICS Selection: Table A.2/2 AND Table A.8/2 AND Table A.13/3
	TC reference: TC_LLC_OBU_BI_04
	Initial condition: OBU initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends an LPDU, containing an ACn command with Poll bit set to P=1, and with broadcast LID. 2. Verify IUT ignores the received LPDU. 3. Repeat steps 1. and 2. for all possible values of a multicast LID instead of the broadcast LID. 4. Repeat step 1. with valid private LID. 5. Verify IUT is not blocked by the pervious erroneous commands, but replies correctly. 	
TP/LLC/OBU/BI/05	Verify that the OBU can detect and manage an invalid LPDU, containing a fractional number of octets in length.
	Reference: EN 12795 [1], clause 8.3.5
	PICS Selection: Table A.2/2 AND Table A.8/1
	TC reference: TC_LLC_OBU_BI_05
	Initial condition: OBU not initialized
Stimulus and Expected Behaviour:	
<ol style="list-style-type: none"> 1. Tester sends UI command carrying a BST with a length that is not an integer multiple of one octet. 2. Verify IUT ignores the received LPDU. 3. Tester sends valid UI command carrying a BST. 4. Verify IUT is not blocked by the previous erroneous frame, but responds correctly with VST. 	

TP/LLC/OBU/BI/06	Verify that the OBU can detect and manage an invalid ACn command with P=1 and no LSDU.
	Reference: EN 12795 [1], clause 8.4.3.2
	PICS Selection: Table A.12/6
	TC reference: TC_LLC_OBU_BI_06
	Initial condition: OBU initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends the invalid AC0 command with P=1 but without LSDU. 2. Verify IUT ignores the received LPDU.
TP/LLC/OBU/BI/07	Verify that the OBU can detect and manage duplicate ACn commands.
	Reference: EN 12795 [1], clause 8.4.3.4.2
	PICS Selection: Table A.12/2
	TC reference: TC_LLC_OBU_BI_07
	Initial condition: OBU initialized
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends valid ACn command. 2. Verify IUT sends correct ACn response. 3. Tester repeats step 1. The n-bit shall not toggle. 4. Verify IUT sends the same ACn response as in step 2. 5. Tester sends another valid ACn command (different from that in steps 1 and 3), but with the n-bit toggled. 6. Verify IUT sends correct ACn response.

5.5 LLC test purposes for Road-Side Unit

5.5.1 BV test purposes

Test subgroup objective:

- to test the behaviour of the IUT in relation to syntactically and contextual correct behaviour of the test system.

Test purposes:

TP/LLC/RSU/BV/01	Verify that the RSU can exchange UI commands.
	Reference: EN 12795 [1], clause 8.4.2
	PICS Selection: Table B.2/2 AND Table B.3/2 AND Table B.10/2
	TC reference: TC_LLC_RSU_BV_01
	Initial condition: RSU set up to run a complete application
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Verify IUT sends an UI command containing a BST. 2. Tester replies with an UI command containing a VST. 3. Verify IUT correctly acknowledges the VST with a privately addressed frame.
NOTE: The frame expected in step 3. may be any privately addressed frame.	

TP/LLC/RSU/BV/02	Verify that the RSU can manage ACn commands with correct n-value initialization and n-value sequence
	Reference: EN 12795 [1], clause 8.4.3.1
	PICS Selection: Table B.2/2 AND Table B.8/2 AND (Table B.13/2 OR Table B.13/3) AND Table B.14
	TC reference: TC_LLC_RSU_BV_02
	Initial condition: Tester initialized with RSU. RSU set up to run an application that needs to send at least three ACn commands
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Verify IUT sends an AC0 command as the first ACn command. 2. Tester replies with an AC1 response. 3. Verify IUT sends an AC1 command as the next ACn command. 4. Tester replies with an AC0 response. 5. Verify IUT sends an AC0 command as the next ACn command.
NOTE: The ACn commands may be either for data transmission or for data exchange.	

TP/LLC/RSU/BV/03	Verify that the RSU can correctly manage the re-transmission of ACn command.
	Reference: EN 12795 [1], clause 8.4.3.3
	PICS Selection: Table B.2/2 AND Table B.8/2 AND Table B.12/1
	TC reference: TC_LL_C_RSU_BV_03
	Initial condition: Tester initialized with RSU. RSU set up to run an application that requires at least transmission of two ACn commands
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Verify IUT sends an AC0 command as the first ACn command. 2. Tester responds correctly to the AC0 command. 3. Verify IUT sends an AC1 command as second ACn command. 4. Verify IUT transmits the same AC1 command N11 times. 5. Verify IUT transmits any new command after N11-1 re-transmissions of the AC1 command.
TP/LLC/RSU/BV/04	Verify that the RSU can correctly manage multiple link communications.
	Reference: EN 12795 [1], clause 8.4.3.1
	PICS Selection: Table B.2/2 AND Table B.8/2 AND Table B.12/5
	TC reference: TC_LL_C_RSU_BV_04
	Initial condition: Tester is simulating 3 OBUs. Application in IUT has to exchange at least two ACn messages after initialization with each OBU
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester shall request private uplink windows for all three OBUs simultaneously in the same sequence of public uplink windows. 2. Verify IUT performs correctly the complete transaction consisting of two ACn cycles for every OBU.
TP/LLC/RSU/BV/05	Verify that the RSU can manage late response Procedure I
	Reference: EN 13372 [3], clause 7.2
	PICS Selection: Table B.2/2 AND Table B.15/2 AND Table F.3/1
	TC reference: TC_LL_C_RSU_BV_05
	Initial condition: RSU ready for normal operation of an application. Tester already registered, awaiting request for retrieval of data causing late response.
	Stimulus and Expected Behaviour:
	<ol style="list-style-type: none"> 1. Tester LLC acknowledges application layer request for data retrieval from the OBU, carried in an ACn command with poll bit set to P=1, with the LLC status subfield value NE_OK, but not providing the requested APDU. In the remaining test the tester shall handle correctly all further requests from the RSU immediately. 2. Observe whether IUT resends the request. If yes, tester shall provide missing APDU in the ACn response. 3. Tester sends PrWRq following the next BST. 4. Verify IUT sends PrWA. 5. Tester sends missing APDU, see step 1, in the allocated private uplink window using a UI-command. 6. Verify IUT accepts this late response and continues with the application.

5.5.2 BI test purposes

Test subgroup objective:

- to check the behaviour of the of the IUT in response to invalid messages and behaviour from the test tool.

Test purposes:

TP/LLC/RSU/BI/01	Verify that the RSU can correctly manage corrupted LLC control fields.
	Reference: EN 12795 [1], clauses 8.4.2.1 and 8.3.2.2
	PICS Selection: Table B.2/2 AND Table B.9/1 AND Table B.11/1
	TC reference: TC_LLC_RSU_BI_01
	Initial condition: Tester initialized with RSU
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Verify IUT sends an UI command containing a BST. 2. Tester replies with an UI command containing a VST, where the reserved bits in the LLC control field are set to zero. 3. Verify IUT ignores the received LPDU. 4. Repeat steps 1. through 3. for all remaining invalid combinations of the reserved bits. 5. Repeat step 1. 6. Tester replies correctly with UI command containing a VST. 7. Verify IUT acknowledges VST with a privately addressed command.
TP/LLC/RSU/BI/02	Verify that the RSU can detect and manage an invalid ACn LPDU, containing a fractional number of octets in length.
	Reference: EN 12795 [1], clauses 5.4, 8.3.4, 8.3.5
	PICS Selection: Table B.2/2 AND Table B.8/2
	TC reference: TC_LLC_RSU_BI_02
	Initial condition: Tester initialized with RSU
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Tester sends an invalid LPDU with length different to an integer multiple of one octet. 2. Verify IUT ignores the received LPDU.
TP/LLC/RSU/BI/03	Verify that the RSU can detect and manage an ACn response, not containing a valid response control field.
	Reference: EN 12795 [1], clauses 5.4 and 8.3.5
	PICS Selection: Table B.2/2 AND Table B.8/2
	TC reference: TC_LLC_RSU_BI_03
	Initial condition: Tester initialized with RSU
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Verify IUT sends an AC0 command as the first ACn command. 2. Tester sends an AC1 response, not containing a valid response control field, except for the n-Bit and for the P/F-bit. 3. Verify IUT ignores the received LPDU. 4. Repeat steps 1. through 3. for all missing invalid values of the response control field, but excluding the value which is valid for a UI command.
TP/LLC/RSU/BI/04	Verify that the RSU can detect and manage an ACn response control field with a corrupted ACn response status subfield.
	Reference: EN 12795 [1] clauses 5.4 and 8.3.5
	PICS Selection: Table B.2/2 AND Table B.8/2
	TC reference: TC_LLC_RSU_BI_04
	Initial condition: Tester initialized with RSU
	Stimulus and Expected Behaviour: <ol style="list-style-type: none"> 1. Verify IUT sends an AC0 command as the first ACn command. 2. Tester sends an AC1 response with status subfield different to any of the valid values (OK_OK = 0x00, NE_OK = 0x30, NR_OK = 0x40, 0x10). 3. Verify IUT ignores the received LPDU. 4. Repeat steps 1. through 3. for all missing invalid values of the response status subfield.

TP/LLC/RSU/BI/05	Verify that the RSU can correctly manage an ACn response with invalid sequence number n.
	Reference: EN 12795 [1], clauses 8.4.3.3 and 8.4.3.6
	PICS Selection: Table B.2/2 AND Table B.8/2 AND Table B.12
	TC reference: TC_LLC_RSU_BI_05
	Initial condition: Tester initialized with RSU. Value of N11 parameter is greater than 1. No re-transmission at application level.
Stimulus and Expected Behaviour:	<ol style="list-style-type: none"> 1. Verify IUT sends an AC0 command as the first ACn command. 2. Tester sends an AC0 response. 3. Verify IUT, after expiry of the acknowledgement timer, retransmits the same AC0 command.

Annex A (informative): Test coverage matrix

A.1 Introduction

The following tables show the test purposes coverage with respect to:

- a) Relevant clauses in the base standard; and
- b) PICS statements.

There is one table for OBU and one table for RSU.

The tables are ordered by base standard clauses. When no other indication is given, it is assumed that the referenced clause contains one testable statement. Otherwise, the referenced statement is identified by the order of sentences, list items, or rules specified in the related base standard clause.

A.2 OBU test coverage matrix

Base standard clause	PICS reference	Test purpose
Foreword	None	Nothing to be tested
1 Scope	None	Nothing to be tested
2 Normative References	None	Nothing to be tested
3 Terms and Definitions	None	Nothing to be tested
4 Abbreviations	None	Nothing to be tested
5 Frame structure with LPDU	Table A.3 - Item 1	Implicitly tested in all TPs
5 Frame structure without LPDU	Table A.3 - Item 1	Implicitly tested in all TPs
5 Frame structure physical layer	Table A.3 - Item 1	Implicitly tested in all TPs
5.1 Delimitation with start and end flag	Table A.3 - Item 2	Nothing testable
5.1 Separate end / start flags	Table A.3 - Item 2	N.A.
5.1 Zero bit insertion	Table A.3 - Item 2	Implicitly tested in all TPs
5.2 Link address field - types of LIDs	None	Nothing testable
5.2 Link address field - extension bit	None	Implicitly tested in all TPs
5.2.1 Private LID Range and encoding	Table A.3 - Item 3	TP/MAC/OBU/BI/07 Implicitly tested in several TPs (validity of frame)
5.2.2 Broadcast LID Value and encoding	Table A.3 - Item 4	Implicitly tested in several TPs (validity of frame)
5.2.3 Multicast LID Range and encoding	Table A.3 - Item 5	Implicitly tested (validity of frame)
5.2.3 Multicast LID Value for test purposes	Table A.3 - Item 5	No TPs specified.
5.2.3 Multicast LID Range of values for private use	Table A.3 - Item 5	No TPs specified.
5.3 MAC control field encoding	See base standard clause 7.3.2.1	-
5.4 LPDU encoding	See base standard clause 8.3	-
5.5 Frame Check Sequence	Table A.3 - Item 8 Table A.6 - Item 1 Table A.6 - Item 6	Implicitly tested in several TPs (validity of frame)
5.6 Bit order All except FCS	Table A.3 - Item 9	Implicitly tested in all TPs
5.6 Bit order FCS	Table A.3 - Item 9	Implicitly tested in all TPs
5.7 Zero bit insertion Procedure	Table A.6 - Item 7	Implicitly tested in all TPs
5.7 Zero bit insertion Abort sequence	Table A.6 - Item 7	TP/MAC/OBU/BI/04 TP/MAC/OBU/BI/05
6 One broadcast SAP in FE	None	N.A., RSU test

Base standard clause	PICS reference	Test purpose
6 One private SAP in FE per ME known to FE	None	N.A., RSU test
6 One broadcast SAP in ME	Table A.2 - Item 1	Implicitly tested
6 One optional private SAP in ME	Table A.2 - Item 2	Implicitly tested
6 Multiple optional multicast SAPs in ME	Table A.2 - Item 3	No TPs specified.
6 Downlink communication	Table A.1 - Item 1	Implicitly tested
6 Uplink communication	Table A.1 - Item 2 Table C.1 - A.2 Item 2	Implicitly tested
6.1 Broadcast SAP establishment	None	Implicitly tested
6.2 Mobile private SAP establishment Request from application layer	None	Implicitly tested
6.2 Mobile private SAP establishment LID generation by application layer	None	Implicitly tested
6.2 Mobile private SAP establishment Usage of private LID in uplinks	None	Implicitly tested
6.3 Fixed private SAP establishment	None	N.A., RSU test
7 MAC data service	None	All MAC TPs
7.1 MAC sublayer architecture	None	Nothing testable
7.2 MAC service primitives	None	These service primitives are not testable
7.2.1.1 F-MA-DATA.request Usage	None	Nothing testable
7.2.1.1 F-MA-DATA.request LID parameter	None	Nothing testable
7.2.1.1 F-MA-DATA.request LPDU parameter	None	Nothing testable
7.2.1.1 F-MA-DATA.request RR parameter	None	Nothing testable
7.2.1.2 F-MA-DATA.indication Usage	None	Nothing testable
7.2.1.2 F-MA-DATA.indication LID Parameter	None	Nothing testable
7.2.1.2 F-MA-DATA.indication LPDU Parameter	None	Nothing testable
7.2.2.1 M-MA-DATA.request Usage	None	Nothing testable
7.2.2.1 M-MA-DATA.request LID parameter	None	Nothing testable
7.2.2.1 M-MA-DATA.request LPDU parameter	None	Nothing testable
7.2.2.2 M-MA-DATA.indication Usage	None	Nothing testable
7.2.2.2 M-MA-DATA.indication LID parameter	None	Nothing testable
7.2.2.2 M-MA-DATA.indication LPDU parameter	None	Nothing testable
7.3.1 Window management Architecture	None	Nothing testable
7.3.2 MAC control field usage	None	Nothing testable
7.3.2.1 MAC control field for downlink Format	Table A.3 - Item 6	Tested in all TPs
7.3.2.2 MAC control field for uplink Format	Table A.3 - Item 7	N.A., RSU test
7.3.3 Downlink window Minimum LTA T1	Table A.4 - Item 4 Table A.5 - Item 1	TP/MAC/OBU/BV/02
7.3.3 Downlink window Minimum LTA T2	Table A.4 - Item 4 Table A.5 - Item 2	TP/MAC/OBU/BV/04
7.3.3 Downlink window Maximum size N2	Table A.4 - Item 4 Table A.5 - Item 7	TP/MAC/OBU/BV/01 TP/MAC/OBU/BI/06
7.3.4 Uplink Windows Architecture	None	Nothing testable
7.3.4.1 Private Uplink Window Ownership	Table A.4 - Item 2	TP/MAC/OBU/BI/23
7.3.4.1 Private Uplink Window Minimum LTA T3	Table A.4 - Item 2 Table A.5 - Item 3	TP/MAC/OBU/BV/05

Base standard clause	PICS reference	Test purpose
7.3.4.1 Private Uplink Window Maximum start time T4a	Table A.4 - Item 2 Table A.5 - Item 4	TP/MAC/OBU/BV/05
7.3.4.1 Private Uplink Window End of frame	Table A.4 - Item 2	N.A., RSU test
7.3.4.1 Private Uplink Window Maximum size N3	Table A.4 - Item 2 Table A.5 - Item 8	TP/MAC/OBU/BV/05
7.3.4.2 Public Uplink Windows Number N5 of subsequent windows	Table A.4 - Item 3 Table A.5 - Item 10	Nothing testable
7.3.4.2 Public Uplink Windows Ownership	Table A.4 - Item 3	Nothing testable
7.3.4.2 Public Uplink Windows Maximum number of octets to be transmitted N4	Table A.4 - Item 3 Table A.5 - Item 9	BI test N.A., RSU test BV test implicitly in all TPs
7.3.4.2 Public Uplink Windows Minimum LTA T3	Table A.4 - Item 3 Table A.5 - Item 3	TP/MAC/OBU/BV/03
7.3.4.2 Public Uplink Windows Maximum start time T4b	Table A.4 - Item 3 Table A.5 - Item 5	TP/MAC/OBU/BV/03
7.3.4.2 Public Uplink Windows Fixed duration T5	Table A.4 - Item 3 Table A.5 - Item 6	TP/MAC/OBU/BV/03
7.3.4.3 Random public uplink window selection	Table A.4 - Item 1	TP/MAC/OBU/BV/08
7.4.1 Private medium response flag Values	Table A.6 - Item 5	Nothing testable
7.4.1 Private medium response flag Purpose	Table A.6 - Item 5	Nothing testable
7.4.2 FE MAC procedures	-	N.A., RSU tests
7.4.3.1.1 ME MAC procedures Validity of received frame Delimitation by flags	Table A.6 - Item 1	TP/MAC/OBU/BI/17 TP/MAC/OBU/BI/18
7.4.3.1.1 ME MAC procedures Validity of received frame LID	Table A.6 - Item 1	TP/MAC/OBU/BI/07 TP/MAC/OBU/BI/19 TP/MAC/OBU/BI/20 TP/MAC/OBU/BI/23
7.4.3.1.1 ME MAC procedures Validity of received frame MAC control field	Table A.6 - Item 1 Table E.2 - all items	TP/MAC/OBU/BV/09 TP/MAC/OBU/BI/08 TP/MAC/OBU/BI/09 TP/MAC/OBU/BI/10 TP/MAC/OBU/BI/11 TP/MAC/OBU/BI/12 TP/MAC/OBU/BI/13 TP/MAC/OBU/BI/14 TP/MAC/OBU/BI/15 TP/MAC/OBU/BI/21 TP/MAC/OBU/BI/22
7.4.3.1.1 ME MAC procedures Validity of received frame Integral number of octets	None Requirement missing in base standard!	Tested for LLC in TP/LLC/OBU/BI/02
7.4.3.1.1 ME MAC procedures Validity of received frame Size N2	Table A.5 - Item 7 Table A.6 - Item 1	TP/MAC/OBU/BV/01 TP/MAC/OBU/BI/06
7.4.3.1.1 ME MAC procedures Validity of received frame FCS	Table A.6 - Item 1 Table A.6 - Item 6	TP/MAC/OBU/BI/01 TP/MAC/OBU/BI/02 TP/MAC/OBU/BI/03TP/MAC/OBU/BI/16
7.4.3.1.1 ME MAC procedures Invalid frame handling	Table A.6 - Item 1	See above
7.4.3.1.2 Information transfer	None	Nothing testable
7.4.3.1.3 Private uplink window (re)allocation S-bit procedure	Table A.6 - Item 2	TP/MAC/OBU/BV/06 TP/MAC/OBU/BV/07
7.4.3.1.4 Public uplink window allocation	Table A.6 - Item 3	N.A., RSU test
7.4.3.2.1 Transmission of commands	Table A.6 - Item 4	Tested in several TPs
7.4.3.2.1 Transmission of responses	Table A.6 - Item 4	Implicitly tested in several TPs

Base standard clause	PICS reference	Test purpose
7.4.3.2.1 Private uplink window transmission Temporary storage of frame for retransmission by MAC	Table A.6 - Item 4	TP/MAC/OBU/BV/07
7.4.3.2.2 Private uplink window request First request for command transmission	Table A.6 - Item 5	Implicitly tested in several TPs
7.4.3.2.2 Private uplink window request Request retransmission	Table A.6 - Item 5	TP/MAC/OBU/BI/24
7.4.3.2.2 Private uplink window request Pending frame. Request of additional PrUW in pending frame, i.e. setting of R-bit in frame with LPDU	Table A.6 - Item 5	
7.4.3.2.2 Private uplink window request In PuUW only!	Table A.6 - Item 5 Table E.1 - Item 1	Tested in several TPs
8.1 LLC Architecture and Services	None	Nothing testable
8.1 UI services	Table A.7 - Item 1	Nothing testable
8.1 ACn services	Table A.7 - Item 2	Nothing testable
8.2 LLC service primitives Possible services	None	Nothing testable
8.2.1 DL-UNITDATA.request LID parameter	None	Nothing testable
8.2.1 DL-UNITDATA.request RR parameter	None	Nothing testable
8.2.1 DL-UNITDATA.indication LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK.request LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK.indication LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK.indication data parameter	None	Nothing testable
8.2.2 DL-DATA-ACK-STATUS.indication LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK-STATUS.indication status parameter	None	Nothing testable
8.2.3 DL-REPLY.request LID parameter	None	Nothing testable
8.2.3 DL-REPLY.request data parameter	None	Nothing testable
8.2.3 DL-REPLY.indication LID parameter	None	Nothing testable
8.2.3 DL-REPLY.indication Deletion of previously received data	None	Nothing testable
8.2.3 DL-REPLY-STATUS.indication LID parameter	None	Nothing testable
8.2.3 DL-REPLY-STATUS.indication status parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE.request LID parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE.request data parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE.request Replacement of previously provided data	None	Nothing testable
8.2.3 DL-REPLY-UPDATE-STATUS.indication LID parameter	None	Nothing testable

Base standard clause	PICS reference	Test purpose
8.2.3 DL-REPLY-UPDATE-STATUS.indication status parameter	None	Nothing testable
8.3 LPDU format architecture	None	Nothing testable
8.3.1 C/R bit handling	See base standard clause 7.3.2	-
8.3.2 LLC control field format	Table A.8 - Item 1	see below
8.3.2.1 LLC control field UI command	Table A.8 - Item 1	Tested in several TPs
8.3.2.2 LLC control field ACn commands / responses	Table A.8 - Item 1	Tested in several TPs
8.3.3 LLC status subfield format	Table A.8 - Item 2	Nothing testable
8.3.3 LLC status subfield OK_OK	Table A.13 - Item 1	Nothing testable
8.3.3 LLC status subfield NE_OK	Table A.13 - Item 2	Nothing testable
8.3.3 LLC status subfield NR_OK	Table A.13 - Item 3	Nothing testable
8.3.3 LLC status subfield RS_OK	Table E.3 - Item 1	Nothing testable
8.3.4 Information field size	None	Erroneous statement in base standard!
8.3.5 Invalid LPDU Handling	None	see below
8.3.5 Invalid LPDU Identified by MAC sublayer	None	Nothing testable
8.3.5 Invalid LPDU fractional size	None	TP/LLC/OBU/BI/02 TP/LLC/OBU/BI/05
8.3.5 Invalid LPDU zero size	None	Not testable
8.3.5 Invalid LPDU invalid control field	None	TP/LLC/OBU/BI/01 TP/LLC/OBU/BI/03
8.3.5 Invalid LPDU invalid type of LID	None	TP/LLC/OBU/BI/04
8.3.5 Invalid LPDU No ACn response status subfield	None	BI N.A.: RSU test
8.4.1 UI command	Table A.9 - Item 1 Table A.9 - Item 2	Implicitly tested in all TPs with UI command
8.4.1 AC0 command	Table A.13 - Item 1 Table A.13 - Item 2	Implicitly tested in all TPs with ACn cycle
8.4.1 AC1 command	Table A.13 - Item 3 Table A.13 - Item 4	Implicitly tested in all TPs with ACn cycle
8.4.1 AC0 response	Table A.13 - Item 5 Table A.13 - Item 6	Implicitly tested in all TPs with ACn cycle
8.4.1 AC1 response	Table A.13 - Item 7 Table A.13 - Item 8	Implicitly tested in all TPs with ACn cycle
8.4.2 UI commands purpose	None	Nothing testable
8.4.2.1 Transmitting UI commands P=0, procedure	Table A.9 - Item 1 Table A.10 - Item 1 Table A.10 - Item 2	Implicitly tested in all TPs (VST transmission)
8.4.2.2 Receiving UI commands procedure	Table A.9 - Item 2 Table A.10 - Item 1 Table A.10 - Item 2	TP/LLC/OBU/BV/01
8.4.3 ACn commands / responses interleaving prohibited	None	Not testable
8.4.3.1 State variables State information for each private SAP	Table A.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1 State variables Transmit State Flag V(SI)	Table A.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1 State variables Receive State Flag V(RI)	Table A.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1.1 V(SI) Purpose (detect duplicate response) and Initialization value	Table A.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1.2 V(RI) Purpose (duplicate command)	Table A.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1.3 Creation and deletion of state variables	Table A.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.2 P/F bit procedure	Table A.11 - Item 6	Implicitly tested in all TPs with ACn command cycles

Base standard clause	PICS reference	Test purpose
8.4.3.2 P bit - LSDU Data Link Echo command	Table A.11 - Item 6 Table A.12 - Item 1	TP/LLC/OBU/BV/04
8.4.3.2 P bit - LSDU Transmitting data	Table A.11 - Item 6 Table A.12 - Item 2	TP/LLC/OBU/BV/02
8.4.3.2 P bit - LSDU Exchanging data command	Table A.11 - Item 6 Table A.12 - Item 3	TP/LLC/OBU/BV/03
8.4.3.2 P bit - LSDU Invalid combination command	Table A.11 - Item 6	TP/LLC/OBU/BI/06
8.4.3.2 F bit - LSDU Acknowledgement, no data requested	Table A.11 - Item 6	TP/LLC/OBU/BV/02 TP/LLC/OBU/BV/04
8.4.3.2 F bit - LSDU Acknowledgement, requested data unavailable	Table A.11 - Item 6	TP/LLC/OBU/BV/05
8.4.3.2 F bit - LSDU Acknowledgement, requested data available	Table A.11 - Item 6	TP/LLC/OBU/BV/03
8.4.3.2 F bit - LSDU Invalid combination response	Table A.11 - Item 6	N.A., RSU test
8.4.3.3 Transmitting ACn command Setting of n-bit	Table A.11 - Item 1	Implicitly tested in all TPs with ACn cycle
8.4.3.3 Transmitting ACn command Retransmission procedure Acknowledgement timer	Table A.11 - Item 1	N.A., RSU test
8.4.3.3 Transmitting ACn command Retransmission procedure Transmission count variable	Table A.11 - Item 1	N.A., RSU test
8.4.3.3 Transmitting ACn command Maximum number of retransmissions N11 - 1	Table A.11 - Item 1	N.A., RSU test
8.4.3.3 Transmitting ACn command Maximum value of N13 of acknowledgement timer	Table A.11 - Item 1	N.A., RSU test
8.4.3.4 Receiving ACn command Procedure to detect duplicate commands	Table A.11 - Item 2	see below
8.4.3.4.1 Non-duplicate ACn command V(RI) value assignment	Table A.11 - Item 2	TP/LLC/OBU/BV/02 TP/LLC/OBU/BV/03 TP/LLC/OBU/BV/04
8.4.3.4.1 Non-duplicate ACn command Response transmission	Table A.11 - Item 2	Implicitly tested in all TPs with ACn cycle
8.4.3.4.1 Late response Procedure I	Table E.4 - Item 1 Note: only provided by 13372	TP/LLC/OBU/BV/05
8.4.3.4.2 Duplicate ACn command basic procedure	Table A.11 - Item 2	TP/LLC/OBU/BI/07
8.4.3.5 Transmitting ACn responses n bit procedure	Table A.11 - Item 3	TP/LLC/OBU/BV/02 TP/LLC/OBU/BV/03 TP/LLC/OBU/BV/04
8.4.3.6 Receiving acknowledgement procedure to identify valid n-bit	Table A.11 - Item 4	Implicitly tested in all TPs with ACn cycle
8.4.3.6 Receiving acknowledgement Valid n-bit procedure	Table A.11 - Item 4	Implicitly tested in all TPs with ACn cycle
8.4.3.6 Receiving acknowledgement procedure for invalid n-bit	Table A.11 - Item 4	Implicitly tested in all TPs with ACn cycle
8.4.3.7 N11	None	Nothing testable
8.4.3.8 N13	None	Nothing testable
8.4.4 Bit order	None	Implicitly tested in all TPs
A Data link layer parameter values	See above where parameter is used	Used in TPs above
B Data link layer overhead	None	Informative
C Evolution of MAC sequence bit	None	Informative
D Address establishment	None	Informative
E A-deviations	None	Informative

A.3 RSU test coverage matrix

Base standard clause	PICS reference	Test purpose
Foreword	None	Nothing to be tested
1 Scope	None	Nothing to be tested
2 Normative References	None	Nothing to be tested
3 Terms and Definitions	None	Nothing to be tested
4 Abbreviations	None	Nothing to be tested
5 Frame structure with LPDU	Table B.3 - Item 1	Implicitly tested in all TPs
5 Frame structure without LPDU	Table B.3 - Item 1	Implicitly tested in all TPs
5 Frame structure physical layer	Table B.3 - Item 1	Implicitly tested in all TPs
5.1 Delimitation with start and end flag	Table B.3 - Item 2	Nothing testable
5.1 Separate end / start flags	Table B.3 - Item 2	No TPs specified.
5.1 Zero bit insertion	Table B.3 - Item 2	Implicitly tested in all TPs
5.2 Link address field - types of LIDs	None	Nothing testable
5.2 Link address field - extension bit	None	Implicitly tested in all TPs
5.2.1 Private LID Range and encoding	Table B.3 - Item 3	TP/MAC/RSU/BI/08 Implicitly tested in several TPs (validity of frame)
5.2.2 Broadcast LID Value and encoding	Table B.3 - Item 4	Implicitly tested in several TPs (validity of frame)
5.2.3 Multicast LID Range and encoding	Table B.3 Item - 5	Implicitly tested in several TPs (validity of frame)
5.2.3 Multicast LID Value for test purposes	Table B.3 - Item 5	No TPs specified.
5.2.3 Multicast LID Range of values for private use	Table B.3 - Item 5	No TPs specified.
5.3 MAC control field encoding	See base standard clause 7.3.2.1	-
5.4 LPDU encoding	See base standard clause 8.3	-
5.5 Frame Check Sequence	Table B.3 - Item 8 Table B.6 - Item 1 Table B.6 - Item 7	Implicitly tested in several TPs (validity of frame)
5.6 Bit order All except FCS	Table B.3 - Item 9	Implicitly tested in all TPs
5.6 Bit order FCS	Table B.3 - Item 9	Implicitly tested in all TPs
5.7 Zero bit insertion Procedure	Table B.6 - Item 8	Implicitly tested in all TPs
5.7 Zero bit insertion Abort sequence	Table B.6 - Item 8	TP/MAC/RSU/BI/04 TP/MAC/RSU/BI/05
6 One broadcast SAP in FE	None	Implicitly tested
6 One private SAP in FE per ME known to FE	None	TP/LLC/RSU/BV/04
6 One broadcast SAP in ME	Table B.2 - Item 1	N.A., OBU test
6 One optional private SAP in ME	Table B.2 - Item 2	N.A., OBU test
6 Multiple optional multicast SAPs in ME	Table B.2 - Item 3	N.A., OBU test
6 Downlink communication	Table B.1 - Item 1	Implicitly tested
6 Uplink communication	Table B.1 - Item 2 Table D.1 - B.2 Item 2	Implicitly tested
6.1 Broadcast SAP establishment	None	Implicitly tested
6.2 Mobile private SAP establishment Request from application layer	None	N.A., OBU test
6.2 Mobile private SAP establishment LID generation by application layer	None	N.A., OBU test
6.2 Mobile private SAP establishment Usage of private LID in uplinks	None	N.A., OBU test
6.3 Fixed private SAP establishment	None	Implicitly tested
7 MAC data service	None	All MAC TPs
7.1 MAC sublayer architecture	None	Nothing testable
7.2 MAC service primitives	None	These service primitives are not testable

Base standard clause	PICS reference	Test purpose
7.2.1.1 F-MA-DATA.request Usage	None	Nothing testable
7.2.1.1 F-MA-DATA.request LID parameter	None	Nothing testable
7.2.1.1 F-MA-DATA.request LPDU parameter	None	Nothing testable
7.2.1.1 F-MA-DATA.request RR parameter	None	Nothing testable
7.2.1.2 F-MA-DATA.indication Usage	None	Nothing testable
7.2.1.2 F-MA-DATA.indication LID Parameter	None	Nothing testable
7.2.1.2 F-MA-DATA.indication LPDU Parameter	None	Nothing testable
7.2.2.1 M-MA-DATA.request Usage	None	Nothing testable
7.2.2.1 M-MA-DATA.request LID parameter	None	Nothing testable
7.2.2.1 M-MA-DATA.request LPDU parameter	None	Nothing testable
7.2.2.2 M-MA-DATA.indication Usage	None	Nothing testable
7.2.2.2 M-MA-DATA.indication LID parameter	None	Nothing testable
7.2.2.2 M-MA-DATA.indication LPDU parameter	None	Nothing testable
7.3.1 Window management Architecture	None	Nothing testable
7.3.2 MAC control field usage	None	Nothing testable
7.3.2.1 MAC control field for downlink Format	Table B.3 - Item 6	N.A., OBU test
7.3.2.2 MAC control field for uplink Format	Table B.3 - Item 7	Tested in all TPs
7.3.3 Downlink window Minimum LTA T1	Table B.4 - Item 1 Table B.5 - Item 1	TP/MAC/RSU/BV/02
7.3.3 Downlink window Minimum LTA T2	Table B.4 - Item 1 Table B.5 - Item 2	Nothing testable
7.3.3 Downlink window Maximum size N2	Table B.4 - Item 1 Table B.5 - Item 7	N.A., OBU test
7.3.4 Uplink Windows Architecture	None	N.A., OBU test
7.3.4.1 Private Uplink Window Ownership	Table B.4 - Item 2	N.A., OBU test
7.3.4.1 Private Uplink Window Minimum LTA T3	Table B.4 - Item 2 Table B.5 - Item 3	N.A., OBU test
7.3.4.1 Private Uplink Window Maximum start time T4a	Table B.4 - Item 2 Table B.5 - Item 4	N.A., OBU test
7.3.4.1 Private Uplink Window End of frame	Table B.4 - Item 2	N.A., OBU test
7.3.4.1 Private Uplink Window Maximum size N3	Table B.4 - Item 2 Table B.5 - Item 8	TP/MAC/RSU/BV/01 TP/MAC/RSU/BI/06
7.3.4.2 Public Uplink Windows N5 subsequent windows	Table B.4 - Item 3 Table B.5 - Item 10	TP/MAC/RSU/BV/06
7.3.4.2 Public Uplink Windows Ownership	Table B.4 - Item 3	N.A., OBU test
7.3.4.2 Public Uplink Windows Maximum number of octets to be transmitted N4	Table B.4 - Item 3 Table B.5 - Item 9	TP/MAC/RSU/BI/21 BV test implicitly in all TPs
7.3.4.2 Public Uplink Windows Minimum LTA T3	Table B.4 - Item 3 Table B.5 - Item 3	N.A., OBU test
7.3.4.2 Public Uplink Windows Maximum start time T4b	Table B.4 - Item 3 Table B.5 - Item 5	N.A., OBU test
7.3.4.2 Public Uplink Windows Fixed duration T5	Table B.4 - Item 3 Table B.5 - Item 6	N.A., OBU test
7.3.4.3 Random public uplink window selection	Table B.4 - Item 3	N.A., OBU test

Base standard clause	PICS reference	Test purpose
7.4.1 Private medium response flag Values	None	N.A., OBU test
7.4.2.1.1 FE MAC procedures Validity of frame Delimitation by flags	Table B.6 - Item 1	TP/MAC/RSU/BI/18 TP/MAC/RSU/BI/19
7.4.2.1.1 FE MAC procedures Validity of frame Integral number of octets	Table B.6 - Item 1	Tested for LLC in TP/LLC/RSU/BI/02
7.4.2.1.1 FE MAC procedures Validity of frame Private LID	Table B.6 - Item 1	TP/MAC/RSU/BI/07 TP/MAC/RSU/BI/08 TP/MAC/RSU/BI/09 TP/MAC/RSU/BI/10
7.4.2.1.1 FE MAC procedures Validity of frame MAC control field	Table B.6 - Item 1 Table F.1 - all items	TP/MAC/RSU/BV/05 TP/MAC/RSU/BI/11 TP/MAC/RSU/BI/12 TP/MAC/RSU/BI/13 TP/MAC/RSU/BI/14 TP/MAC/RSU/BI/15 TP/MAC/RSU/BI/16 TP/MAC/RSU/BI/20
7.4.2.1.1 FE MAC procedures Validity of frame Maximum size of frame N3	Table B.6 - Item 1 Table B.5 - Item 8	TP/MAC/RSU/BV/01 TP/MAC/RSU/BI/06
7.4.2.1.1 FE MAC procedures Validity of frame Maximum size of frame N4	Table B.6 - Item 1 Table B.5 - Item 9	BV implicitly tested TP/MAC/RSU/BI/21
7.4.2.1.1 FE MAC procedures Validity of frame FCS	Table B.6 - Item 1 Table B.3 - Item 8	TP/MAC/RSU/BI/01 TP/MAC/RSU/BI/02 TP/MAC/RSU/BI/03 TP/MAC/RSU/BI/17
7.4.2.1.1 FE MAC procedures Invalid frame handling	Table B.6 - Item 1	See above
7.4.2.1.2 Information transfer	Table B.6 - Item 2	Nothing testable
7.4.2.1.3 Private uplink window allocation Upon PrWRq	Table B.6 - Item 4	Implicitly tested TP/MAC/RSU/BV/07
7.4.2.2.1 Information transfer	Table B.6 - Item 3	Nothing testable
7.4.2.2.2 Private uplink window allocation LPDU requires immediate response	Table B.6 - Item 4	Implicitly tested TP/MAC/RSU/BV/08
7.4.2.2.2 Private uplink window allocation A bit	Table B.6 - Item 4 Table B.3 - Item 6	BV implicitly tested.
7.4.2.2.2 Private uplink window allocation Private LID	Table B.6 - Item 4 Table B.3 - Item 3	Implicitly tested
7.4.2.2.2 Private uplink window allocation S bit	Table B.6 - Item 4 Table B.3 - Item 6	TP/MAC/RSU/BV/04
7.4.2.2.2 Private uplink window allocation Handling of R-bit in an uplink frame with LPDU		
7.4.2.2.3 Private uplink window reallocation private medium response flag	Table B.6 - Item 5	TP/MAC/RSU/BV/03
7.4.2.2.3 Private uplink window reallocation S bit	Table B.6 - Item 5 Table B.3 - Item 6	TP/MAC/RSU/BV/04
7.4.2.2.4 Public uplink window allocation A bit	Table B.6 - Item 6 Table B.3 - Item 6	Implicitly tested
7.4.2.2.4 Public uplink window allocation Broadcast LID	Table B.6 - Item 6 Table B.3 - Item 4	Implicitly tested

Base standard clause	PICS reference	Test purpose
7.4.2.2.4 Public uplink window allocation Number of windows N5	Table B.6 - Item 6 Table B.5 - Item 10	Implicitly tested
7.4.3 ME MAC procedures	-	N.A., OBU test
8.1 LLC Architecture and Services	None	Nothing testable
8.1 UI services	Table B.7 - Item 1	Nothing testable
8.1 ACn services	Table B.7 - Item 2	Nothing testable
8.2 LLC service primitives Possible services	None	Nothing testable
8.2.1 DL-UNITDATA.request LID parameter	None	Nothing testable
8.2.1 DL-UNITDATA.request RR parameter	None	Nothing testable
8.2.1 DL-UNITDATA.indication LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK.request LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK.indication LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK.indication data parameter	None	Nothing testable
8.2.2 DL-DATA-ACK- STATUS.indication LID parameter	None	Nothing testable
8.2.2 DL-DATA-ACK- STATUS.indication status parameter	None	Nothing testable
8.2.3 DL-REPLY.request LID parameter	None	Nothing testable
8.2.3 DL-REPLY.request data parameter	None	Nothing testable
8.2.3 DL-REPLY.indication LID parameter	None	Nothing testable
8.2.3 DL-REPLY.indication Deletion of previously received data	None	Nothing testable
8.2.3 DL-REPLY-STATUS.indication LID parameter	None	Nothing testable
8.2.3 DL-REPLY-STATUS.indication status parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE.request LID parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE.request data parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE.request Replacement of previously provided data	None	Nothing testable
8.2.3 DL-REPLY-UPDATE- STATUS.indication LID parameter	None	Nothing testable
8.2.3 DL-REPLY-UPDATE- STATUS.indication status parameter	None	Nothing testable
8.3 LPDU format architecture	None	Nothing testable
8.3.1 C/R bit handling	See base standard clause 7.3.2	-
8.3.2 LLC control field format	Table B.8 - Item 1	see below
8.3.2.1 LLC control field UI command	Table B.8 - Item 1	Tested in several TPs
8.3.2.2 LLC control field ACn commands / responses	Table B.8 - Item 1	Tested in several TPs
8.3.3 LLC status subfield format	Table B.8 - Item 2	N.A., OBU test
8.3.3 LLC status subfield OK_OK	Table B.14 - Item 1	N.A., OBU test
8.3.3 LLC status subfield NE_OK	Table B.14 - Item 2	N.A., OBU test
8.3.3 LLC status subfield NR_OK	Table B.14 - Item 3	N.A., OBU test
8.3.3 LLC status subfield RS_OK	Table F.2 - Item 1	N.A., OBU test
8.3.4 Information field size	None	Erroneous statement in base standard!

Base standard clause	PICS reference	Test purpose
8.3.5 Invalid LPDU Handling	None	see below
8.3.5 Invalid LPDU Identified by MAC sublayer	None	Nothing testable
8.3.5 Invalid LPDU fractional size	None	TP/LLC/RSU/BI/02
8.3.5 Invalid LPDU zero size	None	TP/LLC/RSU/BI/06
8.3.5 Invalid LPDU invalid control field	None	TP/LLC/RSU/BI/01 TP/LLC/RSU/BI/03
8.3.5 Invalid LPDU invalid type of LID	None	Tested at MAC layer TP/MAC/RSU/BI/09 TP/MAC/RSU/BI/10
8.3.5 Invalid LPDU No or invalid ACn response status subfield	None	TP/LLC/RSU/BI/04
8.4.1 UI command	Table B.10 - Item 1 Table B.10 - Item 2	TP/LLC/RSU/BV/01
8.4.1 AC0 command	Table B.13 - Item 1 Table B.13 - Item 2	Implicitly tested in all TPs with ACn cycle
8.4.1 AC1 command	Table B.13 - Item 3 Table B.13 - Item 4	Implicitly tested in all TPs with ACn cycle
8.4.1 AC0 response	Table B.13 - Item 5 Table B.13 - Item 6	Implicitly tested in all TPs with ACn cycle
8.4.1 AC1 response	Table B.13 - Item 7 Table B.13 - Item 8	Implicitly tested in all TPs with ACn cycle
8.4.2 UI commands purpose	None	Nothing testable
8.4.2.1 Transmitting UI commands P=0, procedure	Table B.9 - Item 1 Table B.9 - Item 2 Table B.10 - Item 1	Implicitly tested
8.4.2.2 Receiving UI commands procedure	Table B.9 - Item 1 Table B.9 - Item 2 Table B.10 - Item 1	Implicitly tested
8.4.3 ACn commands / responses interleaving prohibited	None	Not testable!
8.4.3.1 State variables State information for each private SAP	Table B.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1 State variables Transmit State Flag V(SI)	Table B.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1 State variables Receive State Flag V(RI)	Table B.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1.1 V(SI) Purpose (detect duplicate response) and Initialization value	Table B.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1.2 V(RI) Purpose (duplicate command)	Table B.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.1.3 Creation and deletion of state variables	Table B.11 - Item 5	Implicitly tested in all TPs with ACn command cycles
8.4.3.2 P/F bit procedure	Table B.11 - Item 6	Implicitly tested in all TPs with ACn command cycles
8.4.3.2 P bit - LSDU Data Link Echo command	Table B.11 - Item 6 Table B.12 - Item 1	No TPs specified
8.4.3.2 P bit - LSDU Transmitting data	Table B.11 - Item 6 Table B.12 - Item 2	No test specified
8.4.3.2 P bit - LSDU Exchanging data command	Table B.11 - Item 6 Table B.12 - Item 3	No test specified
8.4.3.2 P bit - LSDU Invalid combination command	Table B.11 - Item 6	Nothing testable
8.4.3.2 F bit - LSDU Acknowledgement, no data requested	Table B.11 - Item 6	N.A., OBU test
8.4.3.2 F bit - LSDU Acknowledgement, requested data unavailable	Table B.11 - Item 6	N.A., OBU test

Base standard clause	PICS reference	Test purpose
8.4.3.2 F bit - LSDU Acknowledgement, requested data available	Table B.11 - Item 6	N.A., OBU test
8.4.3.2 F bit - LSDU Invalid combination response	Table B.11 - Item 6	N.A., OBU test
8.4.3.3 Transmitting ACn command Setting of n-bit	Table B.11 - Item 1	TP/LLC/RSU/BV/02
8.4.3.3 Transmitting ACn command Retransmission procedure Acknowledgement timer	Table B.11 - Item 1	TP/LLC/RSU/BV/03
8.4.3.3 Transmitting ACn command Retransmission procedure Transmission count variable	Table B.11 - Item 1	TP/LLC/RSU/BV/03
8.4.3.3 Transmitting ACn command Maximum number of retransmissions N11 - 1	Table B.11 - Item 1	TP/LLC/RSU/BV/03
8.4.3.3 Transmitting ACn command Maximum value of N13 of acknowledgement timer	Table B.11 - Item 1	Nothing testable
8.4.3.4 Receiving ACn command Procedure to detect duplicate commands	Table B.11 - Item 2	N.A., OBU test
8.4.3.4.1 Non-duplicate ACn command V(RI) value assignment	Table B.11 - Item 2	N.A., OBU test
8.4.3.4.1 Non-duplicate ACn command Response transmission	Table B.11 - Item 2	N.A., OBU test
8.4.3.4.1 Late response Procedure I	Table F.3 - Item 1 Note: only provided by 13372	TP/LLC/RSU/BV/05
8.4.3.4.2 Duplicate ACn command basic procedure	Table B.11 - Item 2	N.A., OBU test
8.4.3.5 Transmitting ACn responses n bit procedure	Table B.11 - Item 3	N.A., OBU test
8.4.3.6 Receiving acknowledgement Valid n-bit procedure	Table B.11 - Item 4	TP/LLC/RSU/BV/02
8.4.3.7 N11	None	Nothing testable
8.4.3.8 N13	None	Nothing testable
8.4.4 Bit order	None	Implicitly tested in all TPs
A Data link layer parameter values	See above where parameter is used	Used in TPs above
B Data link layer overhead	None	Informative
C Evolution of MAC sequence bit	None	Informative
D Address establishment	None	Informative
E A-deviations	None	Informative

History

Document history		
V1.1.1	August 2006	Publication
V1.2.1	October 2008	Publication